

**TENDER DOCUMENT**  
**(PRICE BID FORMAT)**  
**PART - B**

Name of the work:  
**Barricading at CBU area.**

PART B					
PRICE BID FORMAT					
Name of the work: <u>Barricading at CBU area.</u>					
SL. NO	DESCRIPTION OF ITEM	UNITS	QTY.	RATE	AMOUNT
1.00	<b>RECTANGULAR POLES FOR FENCING:</b> Supplying and fixing MS rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) with 2 nos. of 16mm dia. MS hold fast rods each of length 25cm, including the cost of all materials cutting, bending, scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of Engineer Incharge of the work including providing 2 coats of approved quality paint over one coat of primer/ shop painting (excluding cost of earthwork and concrete).	M	84.00		
2.00	<b>CHAIN LINK FENCING:</b> Providing chain link fencing 50mm size of 8 gauge properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour. leads and lifts and as per the directions of Engineer Incharge of work including two coats of approved quality paint over one coat of primer.	sqm	160.50		
3.00	<b>EARTHWORK EXCAVATION:</b> Earthwork excavation for foundation, culverts, water supply and sanitary lines and electrical conduits etc. either in pits or trenches 1.5m and above in width not exceeding 1.5m depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges and shifting it to the place identified by Engineer Incharge inside factory premises etc complete.	cum	6.05		
4.00	<b>PCC 1:2:4 :</b> Providing and laying in position PCC 1:2:4 using 20mm and downsize graded coarse aggregate and fine aggregate, machine mixed, concrete laid in layers not exceeding 15cm thick, well compacted, in foundation, plinth and cills including cost of all materials, labour, HOM of machinery, curing etc complete.	cum	6.05		
5.00	<b>20MM PLASTERING CM1:4:</b> Providing 20mm thick cement plaster in single coat with cement mortar 1:4 to masonry & concrete surface including rounding off corners wherever required smooth rendering, including providing and removing scaffolding, cost of materials, labour, curing etc., complete.	sqm	10.08		
6.00	<b>FABRICATION OF STRUCTURAL STEEL:</b> Supplying fabricating and erecting MS structure for all spans as per approved design and drawing. The work includes cutting, straightening, placing in positions of MS structural members and welding wherever necessary and applying two coat of enamel paint over one coat of red oxide primer coat to all members including cost of all members, labour charges & hire charges of machineries for cutting, welding, grinding & erection equipments, etc. complete.	MT	1.50		
				Sub Total =	
				GST (if any) =	
				Grand Total =	

(Rupees \_\_\_\_\_.)

Signature of the contractor= \_\_\_\_\_

Name of the contractor = \_\_\_\_\_

Address of the contractor = \_\_\_\_\_

Mobile No. of contractor = \_\_\_\_\_

Email Id of contractor = \_\_\_\_\_