

TENDER DOCUMENT

(PRICE BID FORMAT)

PART - B

Name of the work:

Dismantling existing false ceiling from CPBG bay 1.

NAME OF THE WORK: DSMANTLING EXISTING FALSE CEILING FROM CPBG BAY – 1

Sl. No.	Item description	Units	Quantity	Rate	Amount
1.00	DISMANTLING FALSE CEILING: Dismantling of existing false ceiling comprising gypsum board tiles, aluminium frame work for fixing tiles, including T&P, sorting the dismantled materials and stacking the serviceable materials with all lifts complete and disposal of non-serviceable materials into the identified bins inside the factory premises. including the cost of removal of false ceiling tiles, support strucure,all labour, scaffolding tools and tackles safety equipments (PPEs) etc. complete.	Sqm	1111.50		
2.00	DISMANTLING STEEL STRUCURE: Dismantling and removing of existing strucural steel fabricated for installation of false ceiling. Sorting serviceable and non-serviceable material separately. Shifting and stacking serviceable material to identified store and disposing non-serviceable material to metal scrap yard. including the cost of all materials, welding, gas cutting, scaffolding tools and tackles, safety equipments (PPEs) etc complete.	Sqm	5.00		
				Sub – Total =	
	GST (if any)				
				Grand Total =	

(Rupees _____)

Signature of Contractor = _____

Name of Contractor = _____

Address of contractor = _____

Contact No. of contractor = _____

Email id of contractor = _____