

Schedule - A (Part B)

Price Bid Format

Name of the work: Providing aluminium partition at packing area of Solar PV module bay and BHEL EPD reception.

<u>Sl. No.</u>	<u>Item</u>	<u>Unit</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.00	Removal of old aluminium partition and refixing the same to another location using new Hardwares like clip, rubber, screws, nylon plug, assembly screws, including labour charges for cutting the existing section for suit new location and fixing charges. The required glass and MDF board will be provided by BHEL for Free of Cost. The cost of material apart from glass and MDF board will be under the scope of contractor. The rate is inclusive of all labour, handling of materials, working tools, shifting and stacking of materials etc complete.	sqm	80.00		
2.00	Providing, fabricating, assembling and fixing in position aluminium partitions using Jindal make aluminium sections of Matt finish in combination of plain groove, single groove or double grooves as per requirements each measuring 63.5mm x 38.1mm x 1.5mm thickness, Jindal clips suitable section groove, clip rubber, in combination of 9mm thick prelaminated sheets (providing and fixing) of the make as approved by Engineer Incharge and 5mm thick plain glass of Modi Float /saint gobain / ais glass (providing and fixing), design of prelaminated board and glass will be finalised by Engineer Incharge. Including the cost of all materials, labour, handling, shifting and stacking of materials etc complete.	sqm	120.00		
3.00	Providing, fabricating, assembling and fixing in position Openable/Sliding doors using Jindal aluminium section of door top, Door centre 48mm x 44.45mm, Door bottom 95.25mm x 44.45mm, Door vertical 47.62mm x 44.45mm x 1.5mm thickness, clips, in combination of 9mm thick prelaminated sheets (providing and fixing) of the make as approved by Engineer Incharge and 5mm thick plain glass of Modi Float /saint gobain / ais glass (providing and fixing), design of prelaminated board and glass will be finalised by Engineer Incharge. Including the cost of all materials (door handle, door closer, door stopper and other fixtures and fasteners), labour, handling, shifting and stacking of materials etc complete.	sqm	10.50		
Sub Total =					
Taxes, if any (i)					
(ii)					
(iii)					
Grand Total =					

(Rupees _____)

Signature of the contractor: _____

Name of the Contractor: _____

Address of the contractor: _____

Contact No.: _____

Email Address: _____